## Pedram Abedini Arabani

## Week 3 assignment

Question 1: Week 3 In this week's assignment you should first finlize the composite wall question by finding the heat transfer rate, and then solve the same question while the thickness of the brick is increased to 32 cm and comment on the result

$$\begin{split} R_{1conv=} & (1/h_1*A_{1\;dim}) = (1/10\;w/mc + (0.015 + 0.22 + 0.015)m*1m = 0.4\;C/m \\ R_{Foam} & = (L_{Foam}/\,k_{Foam}*A_{1\;dimen}) = (0.03/\,0.026\;w/mc\;*\;(0.015 + 0.22 + 0.015)m\;*1m \approx 4.615\;c/m \\ R_{plaster\;up} & = R_{plaster\;down} = (L_{plaster\;up}/\,k_p*\,A_{p\;up}) = (\,0.32\;m\,/\,0.22\;w/mc\;*\;(0.015\;m^*\,1m) \approx 96.97\;c/m \\ R_{Brick} & = (\,L_{brick}/\,k_{brick}*\,A_{Brick}) = (0.32\;m\,/\,0.72\;w/mc\;*\,0.22m\;*\,1m) \approx 2.02\;c/w \\ R_{total} & = (1/\,R_{plaster\;up} + R_{Brick} + \,R_{plaster\;down}) = 1/\,516 = 1.94\;c/w \\ R_{plaster\;L} & = R_{plaster\;R} = (0.22\;m\,/\,0.022\;w/mc\;*\;(0.015 + 0.22 + 0.015)m\;*\,1m) = 0.36\;c/w \\ R_{2conv} & = (1/h_2*\,A_1) = (\,1/(\,40\;w/m^2\,c\;*\,(\,0.015 + 0.22 + 0.015)m\;*\,1m) = \,0.16\;c/w \end{split}$$

$$R_{\text{wall}} = 7.83 \text{ c/w}$$
 
$$Q = (T_i - T_{\infty}) / R_{\text{wall}} = 20 \text{ c} - (-10 \text{c}) / 7.83 \approx 3.85 \text{ W}$$

By increasing the thickness of brick, there is not significant effect on total wall resistance

Question 2: You should solve again the simplified wall calculation procedure replacing the glass fiber one with urethane rigif foam andwhile replacing the fiberboard with plywood and find the two R unit values

$$R_{WOOD} = 0.03 + 0.14 + 0.11 + 0.63 + 0.079 + 0.12 \approx 1.11 \text{ m}^2 \text{ c/w}$$
  
 $R_{urethane} = 0.03 + 0.14 + 0.11 + 3.528 + 0.079 + 0.12 = 4.00 \text{ m}^2 \text{ c/w}$